BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

BYATARAYANAPURA DIVISION

KODIGEHALLI SUB DIVISOIN

Name of the Work : **Providing and Fixing Name Boards in Vinayaka and Venkategowda layout in ward no. 7, Byatarayanapura Kodigehalli Sub Division.**

Estimate Cost : **1.50 Lakhs**

P-Code : **1771 of 2012-13**

Estimate No : **AEE/KSD/E.NO/ 180 /2012-13**

ತಾಂತ್ರಿಕ ವರದಿ

ವಿಷಯ:– Providing and Fixing Name Boards in Vinayaka and Venkategowda layout in ward no. 7, Byatarayanapura Kodigehalli Sub Division.

Est.Cost.: 1.50 Lakhs

–****–

ಈ ಮೇಲ್ಕಂಡ ಕಾಮಗಾರಿಯು 2012–13ನೇ ಸಾಲಿನ ಪಿ.ಒ.ಡಬ್ಲೂ. ಕಾರ್ಯಕ್ರಮದಲ್ಲಿ ವಾರ್ಡ್ ನಂ. 7ಕ್ಕೆ ನೀಡಿರುವ ರೂ. 3.00 ಕೋಟಿ ಅನುದಾನದ ಕಾರ್ಯಕ್ರಮದಲ್ಲಿ ರೂ. 1.50 ಲಕ್ಷಕ್ಕೆ ಸೇರ್ಪಡೆಯಾಗಿ ವಾರ್ಡ್ ಮಟ್ಟದ ಸಾರ್ವಜನಿಕ ಕಾಮಗಾರಿ ಸ್ಥಾಯಿಸಮಿತಿಯಿಂದ ಅನುಮೋದನೆಗೊಂಡಿರುತ್ತದೆ.

ಈ ಹಿನ್ನಲೆಯಲ್ಲಿ, ಸದರಿ ಈ ಮೇಲ್ಕಂಡ ಕಾಮಗಾರಿ ನಿರ್ವಹಿಸದ ಸ್ಥಳಗಳಲ್ಲಿ ಹಾಗೂ ವಾರ್ಡ್ ವ್ಯಾಪ್ತಿಯಲ್ಲಿನ ಕ್ರಾಸ್ ರಸ್ತೆಗಳು ಮತ್ತು ಇತರೆ ರಸ್ತೆಗಳಲ್ಲಿ ರಸ್ತೆಯ ಹೆಸರು ಮತ್ತು ಕ್ರಾಸ್‌ರಸ್ತೆ ಹೆಸರನ್ನು ಗುರುತಿಸುವ ಸಲುವಾಗಿ ನೇಮ್ ಬೋರ್ಡ್‌ನ ನಾಮಫಲಕಗಳನ್ನು ಅಳವಡಿಸಬೇಕೆಂದು ಸಾರ್ವಜನಿಕರ ಬೇಡಿಕೆಯ ಮೇರೆಗೆ ಈ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ಈ ಕೆಳಕಂಡ ಐಟಂಗಳನ್ನು ಸೇರಿಸಿಕೊಂಡು ತಯಾರಿಸಿದ್ದು, ಎಂ.ಎಸ್. ಶೀಟ್‌ನ್ ನಾಮಫಲಕ ಕನ್ನಡದ ಅಕ್ಷರಗಳೊಂದಿಗೆ ಪೂರ್ಣಗೊಳಿಸಲು ಅಂದಾಜು ಪಟ್ಟಿಯಲ್ಲಿ ಅಳವಡಿಸಿಕೊಂಡು 2012–13ನೇ ಸಾಲಿನ ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖಾ ದರಪಟ್ಟಿ ಬೆಂಗಳೂರು ವೃತ್ತದ ಎಸ್.ಆರ್. ದರದಲ್ಲಿ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ರೂ. 1.50 ಲಕ್ಷಗಳಿಗೆ ತಯಾರಿಸಲಾಗಿರುತ್ತದೆ.

ಕಿರಿಯ ಅಭಿಯಂತರರು
ವಾರ್ಡ್ ನಂ. 7

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಕೊಡಿಗೇಹಳ್ಳಿ ಉಪವಿಭಾಗ

BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name of work: Providing and Fixing Name Boards in Vinayaka and Venkategowda layout in ward no. 7, Byatarayanapura Kodigehalli Sub Division.

Head of Accound: POW 1771 of 2012-13

Estimate Cost Rs. 1.50 Lakhs

Sl No	Item of work	Unit	No	Length	Breadth	Depth	Quantity	Rate in Rs	Amount in Rs
1	Providing and fixing sign board of size 60x60cm equilateral triangle using M.S sheet 5mm thick with RCC pole of size 0.15x0.15x2.3 mtr made out of cement concrete M 20 proportion using 20mm and down size graded metal machine mixed with 10mm dia main steel bars and 8mm dia stirupps as shown in drawing. The poles shall be embedded in the ground for a depth of 0.6mtrs with cement concreteM 10 proportion. The board shall be fixed as per the drawing and at the place indicated by the Engineering charge of the work. The cost includes excavation, cost of all materials, cost of steel, centering, transportation charges, fixing charges etc., The work shall be carried out as per the detailed specifications, drawings and directions of the Engineer in charge of the work.						Each		
	(P.No271, I.No.37.61 of PW,P&IWTD S.R 2012-13								
			39				39.00	3780.00	**147420.00**
	Basic Rate Rs.	3500.00							
	Add 8% A.W Rs.	280.00							
	Total Rate Rs.	**3780.00**							
2	Miscelleneous & Rounding off								2580.00
							Toatl Rs.		**150000.00**
(Rupees:- One Lakhs Fifty Thousand Only)									

CERTIFICATE:

1 The work spot has been inspected me and the work is found to be necessary.
2 The estimate is prepared as per POW, P&IWTD S.R Bangalore circle for the year 2012-13
3 The Provisions made in the estimate are quite necessary and adequate.
4 The area comes with in the BBMP limits.

Junior Engineer
Ward No. 07

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP

Executive Engineer
Byatarayanapura Division
BBMP

Technical Sanction for Rs. 1.50 lakh one lakh fifty thousand only
under 2012-13 POW p.1771
registered as EE No: 314/12-13 Subject to conditions contained enclosed memo.
No: 314/12-13 Dt. 10-1-13
AE/JE
EE (BTP. Div.)
10/01/2013

ADMINISTRATIVELY SANCTIONED FOR Rs
Rupees one lakh fifty thousand only
Under POW-2012-13 p.1771
Registered as EE ( ) No 39
Subject to conditions contained in enclosed memo EE (Byt) No 702 /9/...
Dt 7-1-13 Estimate A/Sanctioned
JC Alm No 702/2013
dated 7-1-13 Rs 1.50 lakh

Joint Commissioner
(Yelahanka Zone)
BBMP. Bengaluru-92.
7/1/13